



SMITHCO SX2 TWO-AXLE SIDE DUMP

DIMENSIONS:

- 39.5" Frame Length
- 102" Width
- 18" Kingpin Setting

FEATURES:

- Electric Tarp System
- Bolt-on Push Block
- LED Lights

FRAME & TUB:

- High Tensile Tapered Frame
- AR400 Steel Construction
- Trailer Mounted Electric-Over Hydraulic Valve
- Front & Rear Fenders
- 34' Length Tub - Round Bottom
- 23 Cubic Yard Capacity - Level Full
- 31 Cubic Yard Capacity - Heaped
- Low Slung Center Stabilizer/Divider
- Water Tight Tub w/Drain Plugs

UNDERCARRIAGE:

- Neway RL250 Air Ride Suspension
- (2) 25,000#, 77½" Wide Trac Axles
- Outboard Hubs / Cast Drums
- Oil Bath Hubs
- Hub Piloted wheels
- 10-Hole Steel Disc Wheels
- 11R22.5 Radial Tires



31 Cubic Yard Capacity - Heaped

